

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 N.R. 23 West


Marquette COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sections 20 and 21

CORNER MONUMENT 1-inch galvanized pipe with 1/2-inch aluminum cap

DATE MONUMENT PLACED AND WITNESSED August 2, 1962 by A. Metsa and R. Bolz

WITNESSES TO CORNER..... Tamarack 10 N 55 W 32.5 Links



CIRCLE CORNER REGISTERED

Cedar 12 S 34 E 67.5 Links

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner was set from the two original tamarack BT's. The one to the SW was standing, still green with upper face showing distinct scribe marks. The other BT was down but both faces were plain with scribe marks evident. No post standing at location, but found the rotted remains of a downed post buried several inches in duff and the well preserved point upright in the wet muck. This undoubtedly was the point of the original post.

SURVEYOR'S SEAL

SIGNED

Aune A. Metsa
REGISTERED LAND SURVEYOR

DATE

8/9/62