

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 N N.R. 23 W


Marquette COUNTY

DESCRIPTION OF CORNER Section Corner common to 19, 20, 29 and 30

CORNER MONUMENT One-inch galvanized pipe with 1/2-inch brass cap

DATE MONUMENT PLACED AND WITNESSED September 28, 1961

WITNESSES TO CORNER..... Red Maple 12" S82 W 51.5 links



White Pine 14" N 66 W 33 links

Red Maple 14" N 20 E 68 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set from the original hemlock bearing tree. The hemlock had fallen with the face down, but sawing off the butt and rolling over the section uncovered the face. The scribe marks showed very plainly. The rotted stump of the spruce bearing tree was evident. An old birch tree about 6 feet from the corner location had been marked for the corner. There was no post in evidence at this corner. Corner was set by A. Motes and W. Oliver.

SURVEYOR'S SEAL

SIGNED

A. Motes
REGISTERED LAND SURVEYOR

DATE

Oct 3, 1961