

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N N.R.'s 23 & 24 W


Margaretta COUNTY

DESCRIPTION OF CORNER Section Corner Common to 16, 19, 24 and 13

CORNER MONUMENT 1-inch galvanized pipe with 4-inch brass cap

DATE MONUMENT PLACED AND WITNESSED September 29, 1961

WITNESSES TO CORNER..... Red Maple 7" S 64 W 51.5 links



CIRCLE CORNER REGISTERED

White Pine 10" N 33 W 70.0 links

Yellow Birch 10" N 3 E 45.0 links

AND

Balsam 7" due east 9.0 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set from the original B.T.'s. The maple B.T. was down with both faces very plain but rotted to the point where the scribe marks were obliterated. One of the hemlock B.T.'s still showed a face on the stump, but no scribe marks. The other two hemlock B.T.'s were in evidence as badly decayed stumps. Size, species, bearings, and distances fitted all B.T.'s. Distance to stump edge to east cheeks. A soft maple about 12 feet from the proper location had been squared for a corner. A squared post, 10 to 15 years old had been set next to the maple B.T., but the proper bearing and distance apparently was unknown to the cruiser who had set the post. Corner was set by A. Metea on September 29, 1961.

SURVEYOR'S SEAL

SIGNED

Alex A. Metea
REGISTERED LAND SURVEYOR

DATE

Oct 4, 1961