

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45. NR. 23. W.


Marquette COUNTY

DESCRIPTION OF CORNER Section Corner Common to Sections 25, 26, 35 & 36

DESCRIPTION OF CORNER MONUMENT One-inch galvanized pipe with four-inch brass cap.

Date monument placed and Witnessed 1/29/62 by A. Metsa and W. Oliver

WITNESSES TO CORNER



Cedar 7" S58E 36 links

Soft Maple 8" S19W 7 links

Soft Maple 6" S76W 20 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set from stump of original white pine bearing tree. Part of the scribe marks showed distinctly. No evidence of the other bearing tree was evident under the snow. A square post had been set in proper direction from B.T. but not at the right distance. Corner checks with swamp edges to east and to north.

SURVEYORS SEAL

SIGNED *A. Metsa*
REGISTERED LAND SURVEYOR

DATE 4/11/62