

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. _____ E. _____ S., R. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION <u>36</u>	T. <u>45</u> N. _____ E. _____ S., R. <u>R23</u> W. _____	<u>1, 2, 7 Ref.</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____	N. _____ E. _____ S., R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on July 8, 1980 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1 West 1/16 on the north section line - Section 36; not previously established.
- 2 East 1/16 corner on the north section line - Section 36; not previously established.
- 7 Ref. Ref. Monument set 1.8' east of the north 1/16 corner on the east section line of Section 36; not previously established.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- 1 Set M.P.O.L. between the N.W. section corner and the N.  $\frac{1}{4}$  corner of Section 36.
- 2 Set M.P.O.L. between the N.  $\frac{1}{4}$  corner and the N.E. section corner of Section 36.
- 7 Ref. Set 1.8' east of the position for the N. 1/16 (M.P.O.L. between the E.  $\frac{1}{4}$  corner and the N.E. section corner of Section 36). The 1/16 corner falls in an 18" H. Maple tree.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- All - 1" pipe, 4" aluminum cap.
- 1 4" H. Maple - N81°E - 4.8'; 6" H. Maple - S89°W - 3.7'; 14" Hemlock - N4°W - 40.8'; 6" H. Maple - S32°E - 17.0'.
  - 2 12" Hemlock - S60°E - 14.0'; 8" H. Maple - S11°E - 5.0'; 16" Spruce - N15°W - 1.5'; 8" Hemlock - N86°W - 26.7'.
  - 7 Ref. 18" H. Maple - N73°W - 1.3'; 5" Y. Birch - N48°E - 9.5'; 9" Y. Birch - S62°E - 9.6'; 19" H. Maple - S17°W - 13.0'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 1-26-81  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558