

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. S., R. <u>23</u> E. W.	<u>L-11, M-11, M-12</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on July 8, 1980 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- L-11 North  $\frac{1}{4}$  corner - Section 36; Wood Post, Sugar 15 - S55°W - 10 lks.; Fir 10 - N7°E - 26 lks
- M-11 N.E. section corner - Section 36; Wood Post, Birch 10 - S68°E - 37 lks.; Hemlock 12 - N59°W - 19 lks.; Birch 12 - S47°W - 28 lks.
- M-12 East  $\frac{1}{4}$  corner - Section 36; Wood Post, Maple 7 - S50°W - 14 lks.; Fir 8 - N44°E - 11 lks.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- L-11 Set M.P.O.L. between the NE and NW section corners of Section 36.
- M-11 Found old square post - remains of N.W. O.B.T. stump including a small piece of the lower face with scribing. Y. Birch stump in place for S.W. O.B.T. Bearings and distances good.
- M-12 Set M.P.O.L. between the N.E. and S.E. section corners of Section 36. No sign of O.B.T.s.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- ALL 1" pipe, 4" aluminum cap
- L-11 8" H. Maple - N55°E - 6.0'; 6" H. Maple - S76°E - 18.4'; 6" H. Maple - S35°E - 12.0'; 8" H. Maple - N58°W - 17.4'.
  - M-11 7" Hemlock - S18°E - 29.7'; 4" Cedar - S43°W - 24.8'; 12" Hemlock - N11°W - 41.6'; 4" Cedar - N79°E - 12.35'.
  - M-12 8" H. Maple - N82°W - 16.1'; 5" H. Maple - N54°E - 19.8'; 9" H. Maple - S83°E - 9.3'; 10" H. Maple - S36°W - 19.1'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 1-26-81  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558