

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. S., R. 24 E. W.	F-6, G-6
2. PROPERTY CONTROLLING IN SECTION	16, T. 45 N. S., R. 24 E. W.	4, 9
3. MISCELLANEOUS PROPERTY IN SECTION	, T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

**MARQUETTE
Co.**

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on December 1, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- F-6 Center of section; not previously established.
- G-6 East 1/4 corner; Wood post - Hem 13 - S75°E - 7 lks.; Hem 10 - S81°W - 23 lks. nothing found.
- 4 1/16 corner center of N.W. 1/4; not previously established.
- 9 East 1/16 corner on E-W 1/4 line; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- F-6 Set at intersection of N-S and E-W 1/4 lines.
- G-6 Set monument at old fence corner - fits G.L.O. record call to a pond 1.80 chs. south, and is compatible with other corner locations in the area.
- 4 Set at intersection of N-S and E-W 1/16 lines in the N.W. 1/4 of section 16 by closed traverse.
- 9 Set M.P.O.L. between the center of section and the east 1/4 corner - falls 31' south of centerline E-W blacktop road and 13' east of centerline blacktop road north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ALL - 1" pipe, 4" aluminum cap.
- F-6 12" r. pine - S34°W - 24.3'; 14" W. pine - N41°W - 33.2'; 16" r. pine - N14°E - 30.2'; 12" r. pine on N-S 1/4 line 400.3' north of ctr. of sec. - on south side of Co. Rd. blased on N & S sides and scribed "L.T."
- G-6 7" w. birch - N69°W - 21.25'; 12" tam. - S60°W - 19.8'; 6" tam. - S8°W - 35.1'
- 4 9" j. pine - N70°E - 60.4'; 8" j. pine East 68.7'; power line, east 44.5'; 13" j. pine S41°E - 22.9'; N.E. corner of shed - S46°W - 9.0'
- 9 5" r. pine - S8°W - 26.7'; 6" r. pine - S85°W - 8.9'; RLS cap in face of guy pole - N41°E - 2.25'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)