

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--                            | LOCATED IN--                           | CORNER CODE NUMBER |  |
|---|--|--------------------|--|
| 1. PUBLIC LAND SURVEY _____                 | T. _____ N. S., R. _____ E. W.         | _____              | <b>MARQUETTE</b><br><b>Co.</b><br><br><small>REGISTER OF DEEDS STAMP AND FILING NUMBER</small> |
| 2. PROPERTY CONTROLLING IN SECTION <u>5</u> | T. <u>45</u> N. S., R. <u>24</u> E. W. | <u>5, 6, 8</u>     |  |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____  | T. _____ N. S., R. _____ E. W.         | _____              |  |
| 4. LOT NO. _____, RECORDED PLAT _____       |  |                    |  |
| 5. PRIVATE CLAIMS _____                     |  |                    |  |

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on October 20 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- 5 - N 1/16 corner on the N-S 1/4 line. Not previously established.
  - 6 - Center 1/16 corner of the N.E. 1/4. Not previously established.
  - 8 - W 1/16 corner on the E-W 1/4 line. Not previously established.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- 5 - Set on line between the position of the N 1/4 corner (which falls in Sporley Lake) and the center of section and proportioned to G.L.O. record measurements.
  - 6 - Set at the computed ctr. of the N.E. <sup>1/4</sup> corner by prop. to G.L.O. recorded measurements.
  - 8 - Set M.P.O.L. between the center of section and the W 1/4 corner.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- All - 1" pipe, 4" aluminum cap
- 5 - 6" soft maple - S7°W - 26.0'; 9" hard maple - S47°E - 36.6'; 17" hem. - N22°E - 40.1'
  - 6 - 6" h. maple - N60°E - 10.2'; 11" Y. birch - S26°W - 42.4'; 12" h. maple - S80°W - 32.7'
  - 8 - 5" spruce - N34°E - 37.5'; 19" r. pine - S24°E - 74.0'; 6" maple - S68°E - 14.3'

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ MICHIGAN REGISTERED LAND SURVEYOR DATE \_\_\_\_\_ (SEAL)