

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>45</u> N. S., R. <u>24</u> E. W.	<u>D-2, E-2</u>
2. PROPERTY CONTROLLING IN SECTION <u>5</u>	T. <u>45</u> N. S., R. <u>24</u> E. W.	<u>9, 15</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

MARQUETTE CO.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on September 27 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 D-2 Ctr. $\frac{1}{4}$ corner; not previously established.

- E-2 East $\frac{1}{4}$ corner; Wood post, Sugar 17-S45°E - 13 lks; fir 9-S27°W - 11 lks.
- 9 E. 1/16 Cor. on E-W $\frac{1}{4}$ line; not previously established.
- 15 W 1/16 Cor. on south Section line; not previously established

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 D-2 Set at the intersection of the N-S & E-W $\frac{1}{4}$ lines.
 E-2 Set on line & prop. to G.L.O. record dist. between the N.E. & S.E. section corners.
 9 Set M.P.O.L. between the ctr. post and the E. $\frac{1}{4}$ corner.
 15 Set M.P.O.L. between the S $\frac{1}{4}$ corner and the S.W. section corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 D-2 1" pipe, 4" aluminum cap; cedar post; 10" maple - S53°W - 5.5'; 9" maple - S19°E - 7.6'; 9" maple - N41°E - 44.0'
 E-2 1" pipe, 4" aluminum cap; 6" iron wood - S62°W - 34.7'; 8" maple - N22°E - 58'; 10" maple - S62°E - 25.7'; cedar post - south - 12'; centerline E-W rd. - north - 18'
 9 1" pipe, 4" aluminum cap; 16" hemlock - S79°W - 38.0'; 6" Bl. cherry - S25°E - 30.9'; 9" maple - N40°W - 72.8'; Centerline E-W rd. - north - 32'
 15 1" pipe, 4" aluminum cap; cedar post; 7" j. pine - N29°E - 3.8'; 6" j. pine - S60°E - 10.9'; 7" j. pine - S81°W - 23.2'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ DATE _____