

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|---------------------------------------|-----------------------------|--------------------|
| 1. PUBLIC LAND SURVEY | T. 45 N. S., R. 24 E. W. | E-3 |
| 2. PROPERTY CONTROLLING IN SECTION | 9, T. 45 N. S., R. 24 E. W. | 1, 3 |
| 3. MISCELLANEOUS PROPERTY IN SECTION | , T. N. S., R. E. W. | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

MARQUETTE
CO.

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on September 23, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- E-3 N.W. Section corner; Wood post - Maple 10 - S65°E - 32 lks.; birch 14 - S31°W - 31 lks.
 - 1 W. 1/16 corner on the north section; not previously established.
 - 3 N. 1/16 corner on West section line; not previously established.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- E-3 Set by double proportion to G.L.O. record using 1/4 cors.; 1/2 mile east and 1 1/2 miles south and section corners 1 mile west and 1 mile north.
 - 1 Set M.P.O.L. between the N.W. section corner and N 1/4 corner.
 - 3 Set M.P.O.L. between the N.W. section corner and the west 1/4 corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- All - 1" pipe, 4" aluminum cap, cedar post.
- E-3 7" j. pine - N56°E - 19.65'; 8" j. pine - S76°W - 14.6'; 3" spruce - N39°W - 49.5'
 - 1 12" cedar - S25°W - 37.4'; 8" spruce - N70°W - 24.9'; 7" cedar - N9°E - 45.15'
 - 3 13" j. pine - S48°E - 66.4'; 8" j. pine - S67°E - 88.1'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ DATE _____