

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T.45... NR... 24W...

----- Marquette ----- COUNTY

DESCRIPTION OF CORNER ----- 1/4 cor. for secs: 19-20 -----

DESCRIPTION OF CORNER MONUMENT ----- 1" Pipe with 4" Brass Cap -----

WITNESSES TO CORNER ----- 15" R. Pine (NBT) S9<sup>o</sup> W 49 Lks. -----

----- 9" R. Oak (NBT) N85<sup>o</sup> E 20<sup>1</sup>/<sub>2</sub> Lks. -----

----- 10" R. Oak (NBT) N12<sup>o</sup> W 60 Lks. -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced from probable W. Pine B.T. bearing N70<sup>o</sup> W 42 Lks. Stp. rotted, no identifying marks. Found 1" Iron Pipe 10 Lks. NW of cor. Several blazes in area. Position fits well with other cors. in this area. Cor. placed and wit. 5/15/59.

SURVEYORS SEAL

*Billy D. Buckler*  
SIGNED \_\_\_\_\_ Billy D. Buckler \_\_\_\_\_ DATE 8/6/59  
REGISTERED LAND SURVEYOR