

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 N.R. 24 W

Marquette COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Section 23 and 26

CORNER MONUMENT 1-inch galvanized pipe with 1/4-inch brass cap


DATE MONUMENT PLACED AND WITNESSED September 18, 1961

WITNESSES TO CORNER..... Sugar Maple 10 N17W 16.5 links

Sugar Maple 12 S33W 69.0 links

Sugar Maple 11 N80W 47.5 links

AND



CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set from the original hemlock B.T. This B.T. was now 24" in diameter, alive, but in bad condition. The trunk was open down the side facing SW due to old lightning damage. Center was hollow with punky wood next to outer shell. The overgrowth over the old face was plain when viewed from inside but scribe marks no longer showed. A decaying balsam, broken off at a stump height, four feet from proper location, had been squared up for corner probably 30 to 50 years ago. Post at this corner had completely rotted away. Corner was found by District Forester, A. Metea, on September 15, 1961.

SURVEYOR'S SEAL

SIGNED

A. Metea
REGISTERED LAND SURVEYOR

DATE

Sept 18, 1961