

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 45 N.R. 24 W


Marquette COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 24 and 25

CORNER MONUMENT 1 - inch iron pipe with 4-inch brass cap

DATE MONUMENT PLACED AND WITNESSED May 2, 1961

WITNESSES TO CORNER..... Soft Maple 6" S 26 W 44 Links



Soft Maple 8" N 65 W 24.5 Links

Hemlock 13" N 18 E 52 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner was set from original BT. Short yellow stub of original BT showed face and scribe marks very plainly. The other BT (maple) was completely rotted away. There was an old squared post in the proper location. Corner was located by Regional Forester Donald Zettle and District Forester Arne Metsa on May 25, 1948 while doing land examinations in the area.

Corner was set by Arne Metsa and William Oliver.

SURVEYOR'S SEAL

SIGNED

Arne A. Metsa  
REGISTERED LAND SURVEYOR

DATE

5/4/61