

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 45 N.R. 24 W


Marquette COUNTY

DESCRIPTION OF CORNER Section Corner Common to Sections 29, 30, 31, and 32

CORNER MONUMENT One-inch galvanized pipe with four-inch aluminum cap

DATE MONUMENT PLACED AND WITNESSED April 12, 1962

WITNESSES TO CORNER..... Black Spruce 12" S 52 E 57.0 links



CIRCLE CORNER REGISTERED

Cedar 8 N 83 E 67.5 links

Cedar 10 N 21 E 42.0 links

AND

Cedar 8 S 5 W 48.5 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set from original birch (white birch) bearing tree. It was a dead stub 18 inches in diameter, 30 feet high. Upper face was plain and showed traces of scribe marks. Bottom face was completely grown over, but chopping it out revealed the face with traces of scribe marks and the notch very distinct. No post found in the area, but uncovered the pointed stub of a post (believed to be the original) preserved in the wet peat 1½ feet below ground level at the proper location. Many blazes and names of cruisers on trees nearby, but apparently the corner had never been re-set before April of 1959 when Arthur Enger, Assistant District Forester, had set a squared 4-inch cedar post in proper location.

SURVEYOR'S SEAL

SIGNED

Arne A. Peterson  
REGISTERED LAND SURVEYOR

DATE

4/16/62