

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MARGUERITE Co.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45N N. S., R. 24W E. W.	G-11
2. PROPERTY CONTROLLING IN SECTION	, T. _____ N. S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 26, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

G-11 - N.E. Sec. Cor. of Sec. 33; wood post Spruce 9" - N10°W - 14 Lks; Cedar 9" - S68°W - 3 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-11 - Set by double proportionate measurement using Sec. Cors. 1 mile South, 1 mile East, 1 mile North and 2 miles West. The Michigan Department of Transportation set a pipe from a found square stake of unknown origin for an M-35 survey. Said pipe is in place S20°W - 114.2' from this Sec. corner. The Hwy. Dept. pipe is not compatible with other known good corner monuments in the area because of this and it's very questionable origin it was not accepted as being in the true Sec. Cor. position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11 - 1" pipe, 4" aluminum cap; 6" Cedar - N23°W 6.5'; 9" Cedar - S11°W - 35.1'; 9" Cedar - S83°W - 36.1'; 8" Cedar - S60°E - 3.8'.

SIGNED BY

David B. Babbitt

DATE

3-7-83

SURVEYOR'S MICHIGAN REGISTRATION NO.

21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: