

# LAND CORNER RECORDATION CERTIFICATE

**MARQUETTE**

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 45N N. S., R. 24W W.	E-11, F-9, F-11
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 3/11, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

E-11 - S.W. Sec. Cor. of Section 28; Wood Post - Spruce 8" - S41°W - 9 Lks; Spruce 8" - N50°E - 18 Lks.

F-9 - N½ Cor. of Sec. 28; marked at mid point on line by Charles Cummings but no description given and no N.B.T.s.

F-11 - S 1/4 Cor. of Section 28; Wood Post - Fir 10" - S9°E - 27 Lks; Spruce 6" - N20°E - 11 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E-11 - Set by double proportionates Mea. using Sec. Cors. 1 mile South - 1 mile North - 1 mile West and two miles East.

F-9 - Set M.P.O.L. between the N.E. & N.W. Sec. Cors. of Sec. 28. Falls between N-35 and the R.R. track. This area has obviously been bulldozed.

F-11 - Set M.P.O.L. between the S.E. and S.W. Sec. Cors. of Section 28.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11 - 1" pipe, 4" aluminum cap; 8" Tamarack - S89°W - 16.2'; 4" Tamarack - S10°W - 8.9'; 4" Tamarack - S70°E - 4.5'; 5" Tamarack - N7°W - 5.3'.

F-9 - 1" pipe, 4" aluminum cap; R/W (concrete) marker S12°W - 48.4'; RR telegraph pole - N10°E - 93.6'; 9" J. Pine - S25°E - 106.8'; Center Line of rail of R.R. East 63.2'.

F-11 - 1" pipe, 4" aluminum cap; 4" B. Spruce - S28°E - 9.2'; 5" B. Spruce - S32°W - 10.7'; 5" B. Spruce - N30°E - 6.4'; 4" B. Spruce - N65°W - 3.0'.

SIGNED BY

*David B. Babbitt*

DATE

9-15-83

SURVEYOR'S MICHIGAN REGISTRATION NO.

21558

(SEAL)