

LAND CORNER RECORDATION CERTIFICATE

MARQUETTE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. <u>45N</u> N. S., R. <u>24W</u> W.	E-12, D-11
2. PROPERTY CONTROLLING IN SECTION.....	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION.....	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 3/11/83, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

E-12 - E $\frac{1}{4}$ Cor. of Section 32; Wood Post - Tam. 11" - N73⁰E - 28 Lks.; Spruce 7" - N79⁰W - 12 Lks.

D-11 - N $\frac{1}{4}$ Cor. of Section 32; Cedar 6" - Quarter Sec. Cor.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E-12 - Set M.P.O.L. between the N.E. and S.E. Cors. of Sec. 32. Several Tam. Stps. in the area but none showing axe marks.

D-11 - Set M.P.O.L. between the N.E. and N.W. Sec. Cors. of Sec. 32. Some down and dead Cedar in the area but could not identify any as the original Cor. tree.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12 - 1" pipe, 4" aluminum cap; 7" Cedar N24⁰W - 23.0'; 7" B. Spruce N51⁰E - 16.8'; 9" Cedar S10⁰E - 19.5'; 5" Tamarack S55⁰W - 6.9'.

D-11 - 1" pipe, 4" aluminum cap; 9" B. Spruce N13⁰W - 12.7'; 9" Cedar S50⁰E - 8.2'; 4" Tamarack S17⁰W - 4.5'; 6" Cedar N55⁰W - 2.9'.

SIGNED BY _____

David B. Babbitt

DATE _____

9-15-83

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: