

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

*MARQUETTE*

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45N</u> N. S., R. <u>24W</u> W.	<u>F-13, E-13</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 3/11/83, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- F-13 - South 1/4 Cor. of Section 33; Wood Post - Spruce 5" - N38°E - 21 Lks.; Tamarack 8" - N49°W - 15 Lks.
  - E-13 - SW Sec. Cor. of Sec. 33; Wood Post - Tamarack 12" - N17°E - 75 Lks; Cedar 6" - N32°W - 20 Lks; Tamarack 4" - S64°E - 28 Lks.; Tamarack 5" - S18°W - 20 Lks.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- F-13 - Found stump of Tamarack O.B.T. showing hack mark and overgrowth on the B.T. blaze. Nothing left above the hack mark. Set Mon. 9.9' - S49°E from O.B.T. stump.
  - E-13 - Found square Cedar post and point of an older post beside it. Not of record but Mea. North and East to known Cors. look good. Searched thoroughly for O.B.T.s but found none. Set Mon. at post.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- F-13 - 1" pipe, 4" aluminum cap; 4" Cedar - S26°W - 2.0'; 7" Cedar - N87°E - 5.7'; 4" Cedar - N4°W - 9.2'; 8" Cedar - N73°W - 10.7'.
  - E-13 - 1" pipe, 4" aluminum cap; 9" Cedar - N34°E - 9.4'; 9" Cedar - S2°W - 12.8'; 8" Cedar - S53°W - 22.8'; 9" Cedar - N12°W - 19.4'.

SIGNED BY David B. Babbitt DATE 9-15-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)