

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> <del>N.</del> <del>S.</del> R. <u>24</u> <del>W.</del> <del>E.</del>	<u>E-6</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 29, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
East 1/4 corner of Sec. 17

Mich. D.N.R. - October 1976  
Replaced 1" pipe w/D.N.R. monument  
N.B.T.s  
4" hemlock - N89<sup>0</sup>W - 9.50'  
6" jack pine - N30<sup>0</sup>W - 13.30'  
9" jack pine - S25<sup>0</sup>E - 8.30'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Re-witnessed D.N.R. monument as set in 1976. County Road comm. has cut all three N.B.T.s marked in 1976.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D.N.R. monument  
4" maple - S64<sup>0</sup>E - 54.2'  
5" maple - N31<sup>0</sup>W - 136.5'  
Plastic R.L.S. cap on iron rod  
R.L.S. #19616 - South - 27.98'  
N.W. corner of  
house foundation - S48<sup>0</sup>E - 230.2'

SIGNED BY David B. Babbitt DATE 9-12-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: