

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Marquette
(County)

Located In:

Corner Code ~~##~~

- | | | | |
|------------------------------------|-------------|--------------|--------------|
| 1. Public Land Survey | T | R | |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S <u>16</u> | T <u>45N</u> | R <u>24W</u> |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

9.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Babbitt, in a field survey on 12/15/87, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

9. East 1/16 corner on the E-W 1/4 line of Section 16. Set DNR Monument Dec. 1, 1976.
 5" r.pine, S8W, 26.7'
 6" r.pine, S85W, 8.9'
 RLS cap in face of guy pole, N41E, 2.25'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

9. Found pipe bent and cap broken off. Set new monument and took two new witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D.N.R. Monument.
 9. Nail and brass tag. Guy pole, S75E, 19.4'
 P.P. - N15E, 62.9'

Signed by David B. Babbitt Date 10-3-88
 Surveyor's Michigan License No. 21558