

1993

COMMISSION

JOB NUMBER: 93300
SHEET NO. : 1-373
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE
(County)

Located In:

Corner Code ##

- 1. Public Land Survey
 - T45N R 25W M-3
 - T45N R 24W A-3
 - T R
 - T R
- 2. Property Controlling in Section
 - S T R
 - S T R
- 3. Miscellaneous Property in Sec.
 - S T R
 - S T R

- 4. Lot No. _____ Recorded Plat _____
- 5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on Friday, December 24, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-3: Section Corner common to Sections 1 and 12, T45N-R25W 1942 - MCRC field book # 712 indicates a 1" iron pipe and and Sections 6 and 7, T45N-R24W. 1844: William A. Burt's jack pine post referenced by:
original survey notes describe the corner monument as a 5" Jack Pine S37W 27.9 ft.
wood post referenced by: 4" Jack Pine N31E 60.0 ft.
9" Spruce Pine N62E, 37 l. Coordinates were also given for this corner.
4" Spruce Pine S65W, 27 l

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 3/4" iron pipe distance South measures 5285.21 as compared to 5284.58 indicated by the Road Commission in 1945. Replaced 3/4" iron pipe with a Marquette County Survey Monument. Peer group ratification 12-13-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced 3/4" pipe with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
10" Jack Pine N83E 45.32 ft.
7" Jack Pine S23E 20.36 ft.
6" Jack Pine S76W 29.63 ft.
10" Jack Pine N17W 59.29 ft.
Monument is 0.20 ft. above grade.
Bk. 4, Pg. 89

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
DEC 30 PM 1:06
1 PAGE 82
LIBER
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by Gerald W. Carlson
Surveyor's Michigan License No. 24589

Date 12-29-93

