

JOB NUMBER: 93300
 SHEET NO. : 1-374
 For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE
 (County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|---------------------------|-----------------------------|
| 1. Public Land Survey | T <u>45N</u> R <u>25W</u> | M-4 |
| | T <u>45N</u> R <u>24W</u> | <u>M-4</u> (A-4) <u>113</u> |
| | T _____ R _____ | |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |

MARQUETTE COUNTY
 MICHIGAN
 RECEIVED FOR RECORD
 1993 DEC 30 PM 1:07
 REGISTER OF DEEDS
 LIBER 1 PAGE 83
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GERALD W. CARLSON, in a field survey on Monday, December 27, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-4: Quarter Corner common to Section 12, T45N-R25W and Section 7, T45N-R24W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by: 3" Spruce Pine N46E, 85 l 2" Spruce Pine N25W, 56 l	1945 - MCRC field book # 697 indicates an iron pipe and jack pine post referenced by: 4" Jack Pine N40E 6.1 ft. 4" Jack Pine S56E 21.2 ft.
--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found a railroad spike distance North measures 2638.88 and distance South measures 2646.33. Road commission in 1945 called for an iron pipe. The railroad spike appears out of position by 4 feet. Set Marquette County Survey Monument equal distance and on line between NE and SE corners of Section 12, T45N-R25W. Peer group ratification 12-13-93.

SURVEY &
 REMONUMENTATION

JAN 11 1999

SECTION

RATIFIED BY PEER GROUP
 P.A. 845 OF 1990

Larry J. Besione
 DATE Dec. 13, 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

- 8" Jack Pine S10W 298.85 ft.
 - 10" Jack Pine N44W 191.28 ft.
 - 8" Jack Pine S83E 366.40 ft.
 - 1/2" x 18" iron with RLS cap N32E 21.70 ft.
- Monument is 0.20 ft. above ground 22 ft. East of a North/South two rut road and 32 ft. South of a crest of a hill in burn area with very few live trees.
 Bk. 6, Pg. 22



Signed by Gerald W. Carlson

Date 12-29-93

Surveyor's Michigan License No. 24589