

1993

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

JOB NUMBER: 93300

SHEET NO. : 1-375

For corners in

Located In: MARQUETTE County Corner Code #

1. Public Land Survey	T <u>45N</u> R <u>25W</u>	M-5
	T <u>45N</u> R <u>24W</u>	<u>M-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
DEC 30 PM 1:07  
1 PAGE 84  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GERALD W. CARLSON, in a field survey on Monday, December 27, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-5: Section Corner common to Sections 12 and 13, T45N-R25W 1942 - Gregory Shadko of the MDNR indicates he set a corner at this position according to a survey on and Sections 7 and 18, T45N-R24W, 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:  
16" Y.Pine S33W, 45 l  
16" Y.Pine N43E, 63 l  
1942 - MCRC field book # 712 indicates concrete measurement set by Mr. Shadko for the Michigan Conservation Commission. No corner accessories were given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found octagonal concrete monument Michigan Conservation Department fish site (1940). Distance South measures 2638.03, distance North measures 5284.58. Left concrete monument as found. Peer group ratification 12-13-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Michigan Conservation Department octagonal concrete monument stamped to identify the corner referenced by nails in:  
9" Jack Pine S18W 18.88 ft.  
13" Jack Pine S84W 46.77 ft.  
10" Jack Pine N29E 63.14 ft.  
7" Jack Pine N86E 20.45 ft.  
Stamped MCR 1993 (Marquette County Remonumentation) on the cap of the existing monument.  
Bk. 6, Pg. 20



Signed by Gerald W. Carlson Date 12-29-93

Surveyor's Michigan License No. 24589