

SURVEYOR
RECORDS

1993

JOB NUMBER: 93300
SHEET NO. : 1-383

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MARQUETTE
(County)

Located in:

Corner Code #

1. Public Land Survey	T 45N	R 25W	M-13
	T 45N	R 24W	A-13 ✓
	T 44N	R 25W	M-1
	T 44N	R 24W	A-1
2. Property Controlling in Section	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1993 DEC 30 PM 1:07
Richard W. Carlson
REGISTERED PROFESSIONAL SURVEYOR

LIBER 1 PAGE 86
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on Friday, December 24, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-13: Section Corner common to Section 36, T45N-R25W; Section 31, T45N-24W; Section 6, T44N-R24W; and Section 1 T44N-25W. 1841: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:
7" W.Pine S58E, 15 l
7" Spruce N78W, 14 l

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - No original G.L.O. evidence found. The corner was placed by proportioned distance North and South to two found Tamarack stumps during an extensive retracement survey conducted by R. Jamros of Benson Forests. The measurement indicated to move Jamros's temporary corner North 0.94 ft. The East and West coordinate was placed by proportionate measurement between the re-established S 1/4 corner of Section 31, T45N-R24W and the S 1/4 corner of Section 36, T45N-R25W. The distance between these corners was 5336.74 ft. (9.26 ft. short of G.L.O.). This moved Jamros's temporary corner West 29.26 ft. The distance from the corner are as follows: West-2635.42 ft., East-2701.31 ft., and North-2636.47 ft. Peer group ratification 12-20-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set an 8.0 ft. long 3/4" diameter iron rebar with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

- 5" Cedar N65E 34.44 ft.
- 6" Cedar S64E 11.29 ft.
- 6" Cedar S44W 32.06 ft.
- 8" Cedar N27W 16.08 ft.

Corner is 0.30 ft. above grade in Cedar swamp.
Bk. 6, Pg. 12

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Signed by Gerald W. Carlson

Date 12-29-93

Surveyor's Michigan License No. 24589

