

SURVEY & REMONUMENTATION

MAR 13 1998

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1997 DEC 30 PM 1:45

SECTION

For corners in

MARQUETTE

(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|---------|---------------------------|------------|
| 1. Public Land Survey | | T <u>45N</u> R <u>24W</u> | <u>B-5</u> |
| | | T _____ R _____ | _____ |
| | | T _____ R _____ | _____ |
| | | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ R _____ | _____ |
| | S _____ | T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ R _____ | _____ |
| | S _____ | T _____ R _____ | _____ |

Patricia A. Menkey
REGISTER OF DEEDS

LIBER **2** PAGE **53**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on DECEMBER 23RD, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
B-5: Quarter Corner common to Sections 7 and 18.

1852: A. Sullivan's original subdivision survey notes describe the corner monument as a wood post referenced by:
17" Y. Pine N87E, 385 L 13" Y. Pine S86-1/4E, 384 L

No further corner information available.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussard
DATE 12/15/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-5: 1997: No original corner evidence found. No other corner evidence found. Original GLO notes indicated that when correcting back from West to East the distance from the S.W. corner to the South 1/4 Corner (in pond) was 38.64 chains, and the distance from the South 1/4 Corner to the S.E. corner was 40.00 chains. The reestablished position of the corner was prorated based upon the original GLO measurements. The Calculated position of the South 1/4 Corner fell in Provost Lake, 240' West of established Witness Corner. There were no nearby line calls available to check. Distance West from established Witness corner is 2805.25' and distance East is 2415.54'. Calculated distances from South 1/4 in lake are as follows: distance West is 2565.25' and distance East is 2655.54'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5: 1997: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.1' above ground. Established new references (to set d.h. nails)

- 15" J. Pine N14W, 74.62'
- 9" R. Pine N90E, 15.45'
- 9" J. Pine S29E, 14.96'
- 12" J. Pine S46W, 9.58'

Conc. filled Pipe W/1/2" Pipe N21W, 64.94'

Note: In light of property ownership concerns bearing trees have only d.h. measuring nails. No bearing trees were blazed and no B.T. Tags or Sign Posts were placed.
Bk. 13, Pg. 89-92



Signed by Gerald W. Carlson

Date 12-24-97

Surveyor's Michigan License No. 24589