

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF -:	LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. S., R. <u>25</u> E. W.	G-8, H-8
2. PROPERTY CONTROLLING IN SECTION <u>22</u>	T. <u>45</u> N. S., R. <u>25</u> E. W.	<u>8</u> GWT
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

MARQUETTE CO.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970. the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on September 15 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- G-8 West $\frac{1}{4}$ corner; 1" iron round bar 24" long; 16" n. pine stump - N65°W - 6.6'; 9" N. pine N6°E - 6.4'.
 - H-8 Ctr. post; Conc. Mon. Set in conjunction with New Swanzy Sub'n. but not recorded.
 - 8 W 1/16 corner on E-W $\frac{1}{4}$ line; not previously established.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- G-8 Set from old NBT's as recorded in the land corner records of the Cleveland Cliffs Iron Co. signed by Ray J. Brotherton and dated 7-21-59. The iron bar was not there.
 - H-8 Witnessed existing conc. mon.
 - 8 Set M.P.O.L. Between the $\frac{1}{4}$ corner & the ctr. post.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- G-8 1" pipe, 4" aluminum cap; 7" R. pine - N39°E - 8.4'; 8" r. pine - S58°W - 36.95'; old N.B.T. 10" R. pine - N6°E - 6.4'; old N.B.T. 16" R.P. stp. - N65°W - 6.6'
 - H-8 4" diameter conc. mon.; 5" J. pine - N20°E - 55.5'; 7" j. pine - N46°E - 78.5'; 6" J. pine - N84°E - 33.6'; conc. plat mon. - south - 139.7'.
 - 8 1" pipe, 4" aluminum cap; 9" j. pine - N21°E - 37.4'; j. pine - S54°E - 45.8'; 11" j. pine - N60°W - 59.0'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ DATE _____