

**LAND CORNER RECORDATION CERTIFICATE**  
**FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

FOR CORNERS OF --:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>45N</u> N. S., R. <u>25W</u> E. W.	<u>C-5</u>
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 28, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
 S.E. Sec. Cor. of Sec. 7

Michigan Department of Conservation Mon.  
 1" pipe with 4" brass cap  
 Set 9-20-50  
 8" spruce - N10° E - 14 Lks.  
 8" W. pine - S42° W - 76 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1" pipe with 4" brass cap. The 8" spruce N.B.T. from the 1950 survey is down and rotten. The 8" W. pine is completely gone. Re-witnessed monument as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Brass cap Cons. Dept. Mon.  
 11" spruce - N59° E - 90.2'  
 5" W. pine - S20° W - 7.4'  
 12" W. pine - N40° W - 18.1'  
 6" W. pine - S35° E - 31.9'  
 & powerline - East - 57'.

SIGNED BY David B. Babbitt DATE 9-12-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)