

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Marquette  
(County)

Located In:

Corner Code ~~≠~~

- |                                    |   |           |   |            |       |            |               |
|------------------------------------|---|-----------|---|------------|-------|------------|---------------|
| 1. Public Land Survey              | T | _____     | R | _____      | _____ |            |               |
|                                    | T | _____     | R | _____      | _____ |            |               |
|                                    | T | _____     | R | _____      | _____ |            |               |
|                                    | T | _____     | R | _____      | _____ |            |               |
| 2. Property Controlling in Section | S | <u>30</u> | T | <u>45N</u> | R     | <u>25W</u> | <u>2,1,8.</u> |
|                                    | S | _____     | T | _____      | R     | _____      | _____         |
| 3. Miscellaneous Property in Sec.  | S | _____     | T | _____      | R     | _____      | _____         |
|                                    | S | _____     | T | _____      | R     | _____      | _____         |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, David Babbitt, in a field survey on 10/11, 19 88, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

2. E 1/16 corner n. line Section 30. No previous record.
1. W 1/16 corner n. line Section 30. No previous record.
3. W 1/16 cor. on E-W 1/4 line Section 30. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

2. Set MPOL between the north 1/4 corner and the NE section corner of Section 30.
1. Set by single proportion to the GLO record between the north 1/4 corner and the NW section corner of Section 30.
8. Set by single proportion to the GLO record between the center of section and the west 1/4 corner of Section 30. Found other irons (property corners?) in the vicinity but not of record. This section has a number of markers of various descriptions apparently not set by proper section subdivision methods.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                            |                            |                          |
|----------------------------|----------------------------|--------------------------|
| 2. DNR Monument.           | 1. DNR Monument            | 8. DNR Monument          |
| NW cor. garage S84E, 65.5' | 22" w.pine, N50E, 39.9'    | 10" w.pine, N68E, 25.65' |
| SW cor. house S14E, 61.6'  | 8" w.birch, S44E, 25.0'    | 12" w.pine, S50E, 24.0'  |
| 14" w.pine, S87W, 26.8'    | 22" w.pine, S70W, 19.5'    | 24" r.pine, S28W, 24.2'  |
| 4" spruce, N47W, 28.0'     | 8" hard maple, N61W, 15.7' | 10" w.pine, N51W, 31.15' |

Signed by David B. Babbitt Date 1-26-89

Surveyor's Michigan License No. 21558