

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Marquette</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>30</u> T <u>45N</u> R <u>25W</u>	<u>6, 5, 4.</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, David B. Babbitt, in a field survey on 10/19/88, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	18	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 6. NE 1/16 corner of Section 30. No previous record.
- 5. N 1/16 corner on N-S 1/4 line of Section 30. No previous record.
- 4. NW 1/16 corner of Section 30. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 6. Set at the computed center of the NE 1/4 of Section 30.
- 5. Set MPOL between the center of Section 30 and the N 1/4 corner of Section 30.
- 4. Set at the computed center of the NW 1/4 of Section 30.

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:

- | | | |
|--|---|--|
| 6. DNR Monument.
6" spruce, N38E, 52.2'
6" w.pine, S11W, 106.6'
16" r.pine, S71W, 114.6'
8" r.oak, N11W, 42.5' | 5. DNR Monument
14" w.pine, N28E, 33.7'
8" r.pine, S22E, 26.35'
8" spruce, S65W, 19.9'
9" r.pine, N41W, 23.8' | 4. DNR Monument
9" w.pine, S58W, 9.2'
8" spruce, N77W, 9.1'
7" spruce, N58E, 26.95'
8" w.pine, S73E, 17.9' |
|--|---|--|

Signed by David B. Babbitt Date 1-26-89
 Surveyor's Michigan License No. 21558