

RF

10 2000

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

1999 DEC 22 AM 11:23

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Patricia H. Monley REGISTER OF DEEDS

For corners in MARQUETTE (County)

Located In: Corner Code #

- 1. Public Land Survey T 45N R 25W A-7 M-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

LIBER R2 PAGE 186

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

I, GERALD W. CARLSON, in a field survey on May 26, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. Row 7, Column A contains a black dot.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: A-7: Corner common to Sections 18 and 19, T45N-R25W, Sections 13 and 24, T45N-R26W.

1844: William A. Burt's original township boundary survey notes describe the corner monument as a wood post referenced by: 14" Sugar S46E, 5L 20" Sugar N39W, 29L

1852: Martin M. Hall's original subdivision survey notes of T45N-R25W, describe the monument as a post and add the following reference: 12" Yellow Birch N55E, 25L

(SEE REVERSE SIDE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: A-7: 1999: No original corner evidence found. Found and accepted a 2" O.D. pipe with a Coupler on top marked by an X with a dimple in the center. Distance North is 2642.64', South is 2593.46'. Checked Line Call: East 1.56 chains (102.96'), Logging Road, course S.E.. Measured East, 104' to old Logging Road course S.E.. Checked Line Call: West 10.0 chains (660'), Top of Ridge 20' course S.E.. Measured West 757' to top of Ridge course S.E..

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: A-7: 1999: Replaced the existing monument with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.5' above ground. Measured found references: 11" Maple S06W 23.90' (GFA NBT-1978) 4" Maple N20W 6.52' (GFA NBT-1978) Established new references: 12" Maple S59E, 29.00' 7" Maple S81W, 27.35'

Green Steel Sign Post w/ Yellow Survey Marker Sign N05E, 2.30'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed. T45N-R25W Corner Search Sheet 99100 FB. 12, Pg. 106-107

RATIFIED BY PEER GROUP P.A. 345 OF 1990 Date 10/25/99



Signed by Gerald W. Carlson Date 12-8-99