

SURVEY & REMONUMENTATION

JOB NUMBER: 94030
SHEET NO. : 1-536

LAND CORNER RECORDATION CERTIFICATE

APR 28 1995 Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1994 DEC 28 PM 5:59

Patricia A. Henley
REGISTER OF DEEDS

For corners in

MARQUETTE
(County)

COMMISSION Located In:

Corner Code #

- | | | | | | | |
|------------------------------------|---|-----|---|-----|-----|--|
| 1. Public Land Survey | T | 45N | R | 25W | D-1 | |
| | T | | R | | | |
| | T | | R | | | |
| | T | | R | | | |
| | T | | R | | | |
| 2. Property Controlling in Section | S | | T | R | | |
| | S | | T | R | | |
| 3. Miscellaneous Property in Sec. | S | | T | R | | |
| | S | | T | R | | |

LIBER **1** PAGE **202**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

I, GERALD W. CARLSON, in a field survey on Monday, December 12, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|--|
| <p>D-1: Quarter Corner common to Section 5, T45N-R25W and Section 32, T46N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:</p> <p>14" Y. Birch N81E, 34 l
22" Y. Birch N43W, 14 l</p> | <p>1993: P. Bressette indicates no evidence of original survey or restoration found. Corner position re-established mid-point and on-line between the Northeast and Northwest corners of Section 5. Witnesses:</p> <p>5" Sugar N32E, 19.0'
8" W. Spruce S51E, 53.4'
6" Sugar S73W, 27.9'
4" W. Spruce N16W, 26.25'
L. 5, R.C. P. 385</p> |
|--|--|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994- Found and accepted DNR monument as placed by P. Bressette. Distance East is 2632.17' (2632.26'-DNR) and distance West is 2632.14' (2632.26'-DNR).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Found Department of Natural Resources iron pipe with aluminum cap in place referenced by nails in:

5" White Spruce N18W 26.41 ft. Bressette NBT
7" White Spruce S51E 53.92 ft. Bressette NBT
6" Maple S72W 27.38 ft. Bressette NBT
8" Maple N56W 37.99 ft.
Steel sign post North 2.0 ft.
Monument is 0.5' above ground and 0.6' West of a 3" diameter wood post. Stamped MCR 1994 on cap of monument (Marquette County Remonumentation).
Bk. 6, Pg. 133

**VALIDATED BY PEER GROUP
P.A. 345 OF 1990**
Lang J. Bussone
DATE Sept 26, 1994

Signed by *Gerald W. Carlson* Date 12-22-94
Surveyor's Michigan License No. 24589

