

SURVEY & REMONUMENTATION

MAR 13 1998

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1997 DEC 26 PM 12:44

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**
MARQUETTE
(County)

Located In: _____ Corner Code # _____

- 1. Public Land Survey T 45N R 25W _____ G-3
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Patricia A. Monley
REGISTER OF DEEDS *pm*

LIBER **2** PAGE **14**
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on AUGUST 6TH, 19 97, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3							●						
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G-3: Section Corner common to Sections 3, 4, 9, and 10.

1852: Martin M. Hall's original subdivision survey notes describe the corner monument as a W. Pine post referenced by:
14" Spruce Pine N31W, 48 L 16" Spruce Pine S89E, 65 L

1942: Survey field notes from M.C.R.C. F.B. #712 (No pg. given) indicate the corner as a set 1" Iron Pipe and Jack Pine Post. Heilala notes that, "All corners (set at this time in this township by the M.C.R.C.) were set in accordance with the U.S. Field Notes where such notes could be used. Locations of lakes, rivers, sloughs, swamps, and hills were considered in locating the corners, and I believe they are set as close as possible to the original locations. In a few places very old squared trees were found decayed and windfallen, but in most places all evidence has been destroyed by forest fires." Established references:

7" J. Pine N81E, 28.5' 5" J. Pine S17E, 25.8'

No Date: The M.C.R.C. Government Corner Index Book (F.B. #643 - Sec. 4) indicates the corner as a 1" Iron Pipe and Jack Pine Post referenced by:

7" J. Pine N81E, 28.5' 5" J. Pine S17E, 25.8'

1945: Survey field notes by Heilala from M.C.R.C. F.B. #697, Pg. 37 indicate that the corner was used in a survey of M.C.R.C. holdings in Section 4. No description of corner object or accessories given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-3: 1997: No original corner evidence found. Found and accepted a 3/4" I.D. Pipe in good condition 1.10' above ground. Found existing references as described in Part C below. Checked Line Call (Course East, 2.52 chains [166.32'] top of ridge 50' N.W.). Measured call: East 166' to a point 50' S.W. of top of ridge. Checked Line Call (Stream 150L course S.S.W., 5.61 chains [370.26'] East of corner. Measured call: East 370' to C/L of 100' wide stream. Checked Line Call (West 4.50 chains [297.00'] top of ledge 25' course S.W.). Measured call: West 297' to a point 25' N.E. of top of ledge. Distance East is 2633.20', distance North is 2629.41' and distance South is 2632.96'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3: 1997: Replaced 3/4" I.D. Pipe with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Measured existing references:

17" J. Pine N80E, 28.90' (to set d.h. nail) (M.C.R.C. NBT)
13" J. Pine S10E, 26.13' (to set d.h. nail) (M.C.R.C. NBT)

Established new references:

16" J. Pine N80W, 22.58' (to set d.h. nail)
10" J. Pine S60W, 17.51' (to set d.h. nail)

Green Steel Sign Post w/ Yellow Survey Marker Sign N.W. 3.0'

Note: All bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.



Signed by Gerald W. Carlson

Date 12-18-97

Surveyor's Michigan License No. 24589