

MAY 19 1999

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

1998 DEC 16 PM 3:21

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MARQUETTE

(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 45N R 25W      G-13 ✓  
                                   T 44N R 25W      G-1  
                                   T \_\_\_\_\_ R \_\_\_\_\_  
                                   T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section                S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec.        S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

*Patricia D. Morley*  
REGISTER OF DEEDS *pm*

LIBER **R 2** PAGE **78**

Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on MAY 4 TH, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
**G-13: Corner common to Sections 33 and 34, T45N-R25W; and Sections 3 and 4, T44N-R25W.**

1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:  
 8" Spruce N24W, 38 L      10" W. Pine N15E, 40 L

1852: Martin M. Hall's original subdivision survey notes for T44N-R25W describe the corner monument as a wood post referenced by:  
 10" Tamarack S25W, 24 L      10" Spruce S55E, 37 L

1941: Survey field notes from M.C.R.C. F.B. #703 (no pg. given), indicate the corner as an "Old Cedar Post - No B.T.'s Found". No accessories given.

1944: Survey field notes by Heilala from M.C.R.C. F.B. #697, pp. 32-33, indicate the corner as an "Old Post in Swamp". Heilala moved the old post as follows: "After looking over the coordinates of section corner ties on Road 553E, I find that the post set for the S.E. Corner of Section 33 has been set 37.6' too far West, so I am resetting same 37.6' East and 2' South, and will use the coordinates shown on the next page." No accessories given.  
**(SEE REVERSE SIDE)**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**G-13: 1998:** No original corner evidence found. Found and accepted a 1" Pipe, 1' high, at the intersection of old brush lines to the East, West, and South. Bearings and distances to remaining 2 found witnesses check reasonably well with those recorded by G. Carlson in L. 5, RC Pg. 40, and L. 001, SM Pg. 443. Other two witness trees were found lying on the ground. Checked Line Call: (Leave Open Swamp, Course S.E., 4.00 chains [264'] South of corner). Measured Call: South, 345', left swamp course S.E.. Distance East is 2677.06. Distance West is 2632.90.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**G-13: 1998:** Replaced found 1" pipe with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is a driveable "swamp" monument, and is 0.5' above ground. Measured to fd. d.h. nails and washers in found references:

- 6" J. Pine N68W, 14.64' (Carlson NBT)      8" J. Pine (dead) N73E, 15.30' (Carlson NBT)
- Established new references:
- 9" Spruce N25E, 64.25'      10" J. Pine S78E, 42.92'
- 5" J. Pine S23E, 34.42'

Green Steel Sign Post w/ Yellow Survey Marker Sign N50E, 2.25'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

RATIFIED BY PEER GROUP  
 P.A. 345 OF 1990

*Larry J. Benson*  
 DATE Nov 2, 1998

Signed by Gerald W Carlson Date 12-14-98

Surveyor's Michigan License No. 24589



MAR 1 9 1999

**G-13:**  
**PART A CONTINUED:**

**SECTION**

No Date: M.C.R.C. Government Corner Index Book #641 indicates the corner as an Old Cedar Post. No accessories given.

No Date: M.C.R.C. Government Corner Index Book #643 indicates the corner as a Squared Spruce Post. No accessories given.

1982: A Certificate of Survey by Gerald W. Carlson P.S. #24589 for Minatorne Corporation (No Liber or pg. given) indicates the corner as a monumented corner. Distance N89-06'-46"E, 2676.24' to the South 1/4 Corner of Section 34. Distance S89-48'-13"W, 2633.16' to the South 1/4 Corner of Section 33. No accessories given.

1982: An LCRC recorded by Gerald W. Carlson P.S. #24589 in L. 5, RC Pg. 40, indicates the corner as a found 1" Pipe, 15" high, and a 4-way blazed tree w/location tag. Set a 2"X2"x4' stake alongside pipe. Referenced by:

6" J. Pine	N70W,	15.00'	6" J. Pine	N07E,	22.09'
8" J. Pine	N71E,	14.82'	5" J. Pine	S15E,	15.76'

1983: A Certificate of Survey recorded by Gerald W. Carlson P.S. #24589 in L. 001, SM Pg. 443, indicates the corner as a found 1" Pipe, 15" high, and location tag. Distance N00-06'-27"E, 2638.38' to the East 1/4 Corner of Section 33. Referenced by d.h. nails in:

6" J. Pine	N70W,	15.00'	6" J. Pine	N07E,	22.09'
8" J. Pine	N71E,	14.82'	5" J. Pine	S15E,	15.76'

1989: The corner is shown on an Easement Description Map for Wisconsin Electric recorded by Gerald W. Carlson P.S. #24589 in L. 129, MR Pg. 344. No description of corner object or accessories given.