

**SURVEY &  
REMONUMENTATION**

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

JOB NUMBER: 94030

**LAND CORNER RECORDATION CERTIFICATE**

SHEET NO. : 1-540

APR 28 1995 Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 28 PH 5:59

For corners in

MARQUETTE  
(County)

COMMISSION

Corner Code ##

*Patricia A. Moulton*  
REGISTER OF DEEDS

1. Public Land Survey	T	45N	R	25W	H-1
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property In Sec.	S		T	R	
	S		T	R	

LIBER 1 PAGE 206  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Sunday, December 4, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

H-1: Quarter Corner common to Section 3, T45N-R25W and Section 34, T46N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a 8" diameter S. Pine referenced by:  
9" S. Pine N44E, 27 l

1941: M.C.R.C. F.B. 712 indicates a set 1" iron pipe and J. Pine post and set new B.T.'s. Distances shown in F.B. 712 (5281.6') indicate set proportionately on line between the N.W. Corner of Section 3 and the N. Quarter Corner of Section 1. New B.T.'s:  
5" J. Pine N81E, 63.0'  
5" J. Pine S60W, 33.4'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1994- Found and accepted iron pipe as set by M.C.R.C. in 1941. Distance East to North East Corner Section 1 is 13190.06' and distance West is 2639.60' as compared to 2640.80' (M.C.R.C.-1941).

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1994 - Replaced 1" diameter iron pipe with a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:  
8" Jack Pine N13E 19.85 ft. GCVN NBT  
8" Jack Pine S62W 33.56 ft. GCVN NBT  
7" Jack Pine N60W 205.10 ft.  
Top of 6' tall gas line marker N83E 105.45 ft.  
Steel sign post North 2.0 ft.  
Monument is 0.2' above ground in clear cut area 150' +/- West of the West edge of pavement of County Road 553  
Bk. 6, Pg. 125

**RATIFIED BY PEER GROUP  
P.A. 345 OF 1990**

*Larry J. Bussone*  
DATE Sept 26, 1994

Signed by Gerald W. Carlson

Date 12-22-94

Surveyor's Michigan License No. 24589

