

SURVEY & REMONUMENTATION

MAR 13 1998

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

1997 DEC 26 PM 12:45

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MARQUETTE
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 45N R 25W H-3
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Patricia A. Hanberg
REGISTER OF DEEDS

LIBER **2 PAGE 17**
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on JULY 22, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3								●					
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-3: Quarter Corner common to Sections 3 and 10.
 1852: Martin M. Hall's original subdivision survey notes describe the corner monument as a Spruce Pine post on ledge 30' high course N.W.. Referenced by:
 12" Spruce Pine S32W, 13 L 8" Spruce Pine N44E, 45 L

1942: Survey field notes from M.C.R.C. F.B. #712 (No Pg. given) indicate the corner as a set 1" Iron Pipe on ledge. Heilala notes that, "All corners (set at this time in this township by the M.C.R.C.) were set in accordance with the U.S. Field Notes where such notes could be used. Locations of lakes, rivers, sloughs, swamps, and hills were considered in locating the corners, and I believe they are set as close as possible to the original locations. In a few places very old squared trees were found decayed and windfallen, but in most places all evidence has been destroyed by forest fires." Established references:
 6" J. Pine S61W, 20.8' 6" J. Pine N76W, 20.7'

RATIFIED BY PEER GROUP
P.A. 345 OF 1990
Larry J. Busone
 DATE 12/8/97

No Date: The M.C.R.C. Government Corner Index Book (F.B. #643 - Sec. 3) indicates the corner as a 1" Iron Pipe on ledge referenced by:
 6" J. Pine S61W, 20.8' 6" J. Pine N76W; 20.7'

No Date: A Right-of-Way Sketch for proposed County Road 553 indicates the corner West of the proposed road. No description of corner object or accessories given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-3: 1997: No original corner evidence found. Found and accepted a 1" diam. Pipe 1.15' high in rock crib located approximately 200' West and 300' North of the intersection of Co. Rd. 553 and K.I. Sawyer access road. Found four existing references that were recently witnessed as described in Part C below. Checked Line Call (East, 2.76 Chains [182.16'] enter swamp course N.W.). Measured Call: East, 110' enter swamp. Checked Line Call (West, 11.24 Chains [741.84'] top fo ledge 40' N.W.). Measured call: 750' to top of ledge. There were no other line calls available to check. Distance East is 2648.73' and distance West is 2633.20'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-3: 1997: Replaced found 1" diam. Pipe with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Measured existing references:
 6" J. Pine N60E, 13.05' (to fd. spike)
 9" J. Pine N32W, 11.08' (to fd. spike)
 6" J. Pine S83W, 29.39' (to fd. spike)
 12" J. Pine S78E, 26.14' (to fd. spike)
 Green Steel Sign Post w/ Yellow Survey Marker Sign S50E, 2.20'

Note: Bearing trees have painted face, butt, and side nail blazes, measuring spikes, and stamped B.T. Tags affixed.



Signed by Gerald W. Carlson Date 12-18-97

Surveyor's Michigan License No. 24589