

MAR 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

1997 DEC 26 PM 12: 45

*Patricia A. Manley*  
REGISTER OF DEEDS

For corners in MARQUETTE Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T 45N R 25W \_\_\_\_\_ H-5  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

LIBER 2 PAGE 18  
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on JULY 22, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-5: Quarter Corner common to Sections 10 and 15.  
1852: Martin M. Hall's original subdivision survey notes describe the corner monument as a Fir post referenced by:  
10" Spruce Pine S60W, 15 L 10" Spruce Pine N55E, 27 L

1942: Survey field notes from M.C.R.C. F.B. #712 (No Pg. given) indicate the corner as a set 1" Iron Pipe and Spruce Post. Heilala notes that, "All corners (set at this time in this township by the M.C.R.C.) were set in accordance with the U.S. Field Notes where such notes could be used. Locations of lakes, rivers, sloughs, swamps, and hills were considered in locating the corners, and I believe they are set as close as possible to the original locations. In a few places very old squared trees were found decayed and windfallen, but in most places all evidence has been destroyed by forest fires." Established references:

6" J. Pine S14E, 29.9' 5" J. Pine N06E, 18.1'

No Date: The M.C.R.C. Government Corner Index Book (F.B. #643 - Sec. 10) indicates the corner as a 1" Iron Pipe and Spruce Post referenced by:

6" J. Pine S14E, 29.9' 5" J. Pine N06E, 18.1'

1988: A Certificate of Survey by Gerald W. Carlson P.S. #24589 indicates the corner as a found 1" Iron Pipe referenced by:

14" J. Pine N48E, 32.56' 10" J. Pine N10E, 18.43' (MCRC NBT)  
14" J. Pine N81E, 19.06' 14" J. Pine S50W, 11.91'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-5: 1997: No original corner evidence found. Found and accepted a 1" iron Pipe undisturbed and plumb 1.91' high located approximately 220' West of Co. Rd. 553. Found four existing references as described in Part C below. Checked Line Call (West, 7.93 Chains [523.38'] stream 60 L S.W.). Measured call: 500' to dried up stream bed. No other nearby line calls were available to check. Distance East is 2635.21' and distance West is 2650.80'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5: 1997: Replaced found 1" Pipe with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Measured existing references:

12" J. Pine N10E, 18.42' (M.C.R.C. NBT)  
16" J. Pine N25E, 32.57' (Carlson NBT)  
15" J. Pine N75E, 19.11' (Carlson NBT)  
15" J. Pine S35W, 11.93' (Carlson NBT)

Green Steel Sign Post w/ Yellow Survey Marker Sign North, 2.0'

Note: Bearing trees were found with face and side blazes. Butt blazes were added and stamped B.T. Tags affixed.



Signed by Gerald W. Carlson Date 12-22-97

Surveyor's Michigan License No. 24589