

**SURVEY &
REMONUMENTATION**

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1994 DEC 29 PM 1:54

Patricia L. Munkley
REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE
APR 28 1995 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Marquette
(County)

COMMISSION Located in:

Corner Code ##

1. Public Land Survey	T 46N R 25W	I-13
	T 45N R 25W	I-1 ✓
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussone
DATE Sept 12, 1994

LIBER **1** PAGE **207**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Michael Mileski

September 94

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-13; Southwest Corner Section 35;

See back of form.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13; Southwest Corner Section 35;

Found no evidence of either U.S. or M.C.R.C. monumentation or accessories. Reestablished the southwest corner of section 35 at proportionate distance along an arc connecting the southeast corner of section 36 and the south one-quarter corner of section 34.

State Plane Coordinates

Grid System - NAD 83

Zone Number - 2111 Michigan North

Units - International Feet

Y = 565332.83767

X = 26143724.77136

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13; Southwest Corner Section 35;

Set 3/4" x 24" iron rod with 3" aluminum cap appropriately stamped as to location.

W1: SE Corner Concrete Light Pad	N10°E	105.34'
W2: North Bolt of Light Pole mkd. with "X"	S44°E	117.67'
W3: Top of Hydrant	S02°W	244.40'
W4: NE Corner Concrete Light Pad	N54°W	28.29'

See sketch on back of form.

Signed by *Michael Mileski*

Date 21 Nov 1994

Surveyor's Michigan License No. 39091