

**SURVEY & REMONUMENTATION**

MAR 13 1998

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

1997 DEC 26 PM 12: 45

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T 45N R 25W \_\_\_\_\_ I-5 \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

*Patricia L. Monbey*  
REGISTER OF DEEDS *pm*

LIBER **2** PAGE **20**  
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on AUGUST 6TH, 19 97, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

I-5: Section Corner common to Sections 10, 11, 14, and 15.  
1852: Martin M. Hall's original subdivision survey notes describe the corner monument as a Spruce Pine post referenced by:  
8" Spruce Pine S53W, 9 L 8" Spruce Pine N61E, 40 L

1942: Survey field notes from M.C.R.C. F.B. #712 (No pg. given) indicate the corner as a found 1" Iron Pipe and Jack Pine Post. Heilala notes that, "All corners (set at this time in this township by the M.C.R.C.) were set in accordance with the U.S. Field Notes where such notes could be used. Locations of lakes, rivers, sloughs, swamps, and hills were considered in locating the corners, and I believe they are set as close as possible to the original locations. In a few places very old squared trees were found decayed and windfallen, but in most places all evidence has been destroyed by forest fires." Established references:

7" J. Pine N46W, 39.5' 6" J. Pine N70E, 30.9'

No Date: The M.C.R.C. Government Corner Index Book (F.B. #643 - Sec. 10) indicates the corner as a 1" Iron Pipe and Jack Pine Post referenced by:

7" J. Pine N46W, 39.5' 6" J. Pine N70E, 30.9'

No Date: The corner is shown on a sketch of County Road 553 of unknown origin. No description of corner object or accessories given.

1981: An LCRC recorded by Glenn C. Van Neste P.S. #27464 in L. 4, RC Pg. 75 indicates the corner as a found 3/4" I.D. Iron Pipe referenced by:

10" J. Pine S47E, 8.82' 12" J. Pine N44W, 39.71' (MCRC NBT)  
6" J. Pine S43W, 4.23' 12" J. Pine N76E, 30.99' (MCRC NBT)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I-5: 1997: No original corner evidence found. Found and accepted a 3/4" I.D. Iron Pipe undisturbed and straight. Found existing references as described in Part C below. There were no nearby line calls available to check. Distance East is 2716.51', distance West is 2635.21' and distance North is 2628.78'.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-5: 1997: Replaced Found 3/4" Pipe with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.30' above ground. Measured existing reference:

13" J. Pine N80E, 31.20' (to fd. nail w/washer) (scribed butt blaze) (M.C.R.C. NBT)  
7" J. Pine S43W, 4.23' (to fd. nail w/washer) (Van Neste NBT)  
21" Multiple Growth J. Pine N44W, 39.61' (to fd. nail w/washer) (M.C.R.C. NBT)

Established new reference:  
8" J. Pine S10E, 11.93' (to set d.h. nail)  
Green Steel Sign Post w/ Yellow Survey Marker Sign N.W., 3'

Note: Stamped B.T. Tags were affixed to existing bearing trees. New bearing tree has painted face, butt, and side nail blazes, d.h. measuring nail, and stamped B.T. Tag affixed. Bk. 12, Pg. 12

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   | ●  |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

RATIFIED BY PEER GROUP  
P.A. 345 OF 1990

*Larry J. Bussme*  
DATE 12/8/97

Signed by Gerald W. Carlson Date 12-18-97

Surveyor's Michigan License No. 24589

