

SURVEY & REMONUMENTATION

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1994 DEC 29 PM 1:54

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

Marquette
(County)

Located In:

Corner Code #

- | | | | | | |
|---------------------------------------|---------|---------------------------|---------|------|---|
| 1. Public Land Survey | | T <u>46N</u> R <u>25W</u> | | J-13 | |
| | | T <u>45N</u> R <u>25W</u> | | J-1 | ✓ |
| | | T _____ R _____ | | | |
| | | T _____ R _____ | | | |
| 2. Property Controlling
in Section | S _____ | T _____ | R _____ | | |
| | S _____ | T _____ | R _____ | | |
| 3. Miscellaneous
Property in Sec. | S _____ | T _____ | R _____ | | |
| | S _____ | T _____ | R _____ | | |

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussone
DATE Sept 12, 1994

LIBER **1** PAGE **208**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Michael Mileski, in a field survey on September 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13; South One-Quarter Corner Section 35;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13; South One-Quarter Corner Section 35;

Reestablished the south one-quarter corner of section 35 at proportionate distance along an arc connecting the southeast corner of section 36 and the south one-quarter corner of section 34.

State Plane Coordinates:

Grid System - NAD 83
Zone Number - 2111 Michigan North
Units - International Feet
X = 565316.71018
Y = 26146362.34501



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13; South One-Quarter Corner Section 35;

Set 2" I.D. x 30" aluminum pipe with 3" aluminum cap (Berntsen A1NB30) appropriately stamped as to location.

Set 1/2"x18" iron rod & cap #39091	N45°E	45.00'
Set 1/2"x18" iron rod & cap #39091	S45°E	45.00'
Set 1/2"x18" iron rod & cap #39091	S45°W	45.00'
Set 1/2"x18" iron rod & cap #39091	N45°W	45.00'
Location Post	North	1.5'

Signed by Michael Mileski Date 21 Nov 1994
Surveyor's Michigan License No. 39091