

**SURVEY &
REMONUMENTATION**

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1994 DEC 29 PM 1:55

Patricia A. Monahan
REGISTER OF DEEDS

For corners in APR 28 1995

Marquette (County) **COMMISSION** Located In: Corner Code #

1. Public Land Survey	T	45N	R	25W	J-3
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Sec.	S		T		R
	S		T		R

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**

Larry J. Bussard
DATE Sept 12, 1994

LIBER **1** PAGE **214**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on September 94, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

J-3; South One-quarter Corner Section 2;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-3; South One-quarter Corner Section 2;

Found Mr. Kazianka's iron pipe and 4" aluminum cap in agreement with his new bearing trees.

State Plane Coordinates:

Grid System - NAD 83
Zone Number - 2111 Michigan North
Units - International Feet
Y = 559987.62983
X = 26146319.73080

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-3; South One-quarter Corner Section 2;

See back of form.



Signed by Michael Mileski Date 21 Dec 1994
Surveyor's Michigan License No. 39091

Ref 6476
Geo
Geo Com

A. Description of original monument and accessories and/or subsequent restoration:

J-3; South One-quarter Corner Section 2;

Originally established during U.S. Survey conducted by Martin Hall, D.S. in 1852 and monumented with a spruce pine post witnessed by a

Spruce Pine 8 N60°W 33 lks.
and a
Spruce Pine 10 S41°E 8 lks.

This corner was remonumented with a 1" iron pipe and jack pine post on 1 May 1942 by the Marquette County Road Commission. Refer to M.C.R.C. field book 712 pages 20 and 28. The M.C.R.C. noted the following new bearing trees:

8" Jack Pine N25°E 18.1'
4" Jack Pine S13°W 37.4'

On 13 November 1968 Edward Kazianka, P.S. recovered the M.C.R.C.'s iron pipe and remonumented the corner with a 1" x 36" iron pipe with 4" aluminum cap. Mr. Kazianka noted the following new bearing trees:

10" Jack Pine S35°W 81 lks.
12" Jack Pine N37°W 65½ lks.
Jack Pine stump S17°W 56½ lks.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-3; South One-quarter Corner Section 2;

Replaced found iron pipe with 2" I.D. x 30" aluminum pipe with 3" aluminum cap appropriately stamped as to location.

Set 60d spike	W/side	10" Jack Pine	N14°E91.98'
Set 60d spike	N/side	10" Jack Pine	S69°E65.55'

The above two new bearing trees marked with upper and lower face blazes and scribed "NBT".

Set 60d spike	E/side	13" Jack Pine	S32°W53.46' (Kazianka NBT)
Set 60d spike	NE/side	18" Jack Pine	N40°W30.07' (Kazianka NBT)
		Location Post	South 1.5'