

**SURVEY & REMONUMENTATION**  
**LAND CORNER RECORDATION CERTIFICATE**

MARQUETTE COUNTY  
 MICHIGAN  
 RECEIVED FOR RECORD

1994 DEC 29 PM 1:55

For corners in APR 28 1995

Marquette (County) Located In: COMMISSION Corner Code # K-2

1. Public Land Survey	T	<u>45N</u>	R	<u>25W</u>	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Sec.	S	_____	T	_____	R
	S	_____	T	_____	R

**RATIFIED BY PEER GROUP  
 P.A. 345 OF 1990**

*Larry J. Bussone*  
 DATE Sept 12, 1994

*Patricia A. Mearns*  
 REGISTER OF DEEDS

LIBER **1** PAGE **212**  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Michael Mileski, in a field survey on September 94, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

K-2; East One-quarter Corner Section 2;  
 See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-2; East One-quarter Corner Section 2;  
 Found no evidence of either U.S or M.C.R.C. monumentation or accessories. Reestablished corner on line between the northeast corner of section 2 and the southeast corner of section 2 at a distance proportional to the U.S. record.

State Plane Coordinates:  
 for E $\frac{1}{4}$  Cor. 2-45-25  
 Grid System - NAD 83  
 Zone Number - 2111 Michigan North  
 Units - International Feet  
 Y = 562617.49454  
 X = 26148985.16316

State Plane Coordinates:  
 for Witness Corner  
 Grid System - NAD 83  
 Zone Number - 2111 Michigan North  
 Units - International Feet  
 Y = 562617.86217  
 X = 26148865.18196

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2; East One-quarter Corner Section 2;  
 See back of form.



Signed by *Michael Mileski* Date 21 Nov 1994

Surveyor's Michigan License No. 39091

9  
15  
Dec 6476  
2003

A. Description of original monument and accessories and/or subsequent restoration:

K-2; East One-quarter Corner Section 2;

Originally established during U.S. Survey conducted by Martin Hall, D.S. in 1852 and monumented with a tamarack post witnessed by a Tamarack 16 N17°W 7 lks. and a Spruce 12 S56°E 40 lks.

This corner was remonumented with a 1" iron pipe and spruce post on 29 April 1942 by the Marquette County Road Commission at a position intended to be on line between the southeast corner of section 2 and the northeast corner of section 2 at a distance of 2648.90 feet from the southeast corner of section 2. The M.C.R.C length of the east line of section 2 was determined to be 5328.92 feet. The record U.S. length of this line is 80.46 chains with the south one-half mile being 39.86 chain

If the U.S. length of the south one-half mile of the east line of section 2 was assumed to be 40.00 chains, then  $(40.00/80.46)(5328.92') = 2649.23$  feet which is close to the distance determined from the M.C.R.C. field notes. Refer to M.C.R.C. field book 712 pages 18 & 17.

The M.C.R.C. noted the following new bearing trees:

- 6" Spruce S77°W 22.7'
- 5" Spruce N66°E 28.2'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2; East One-quarter Corner Section 2;

Set 2" I.D. x 30" aluminum pipe with 3" aluminum cap (Berntsen A1NB30) appropriately stamped as to location at the corner position.

Set 60d spike	E/side	14" Tamarack	N37°E	41.65'
Set 60d spike	S/side	18" Tamarack	S79°E	40.73'
Set 60d spike	W/side	9" Jack Pine	S37°W	42.39'
Set 60d spike	N/side	7" Tamarack	N89°W	23.07'
		Location Post	East	1.5'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".

Also established witness corner monumented with a 2" I.D. X 30" aluminum pipe with 3" aluminum cap appropriately stamped as to location on the east-west one-quarter line of section 2 a distance of 120.00 feet westerly of the one-quarter corner.

Set 60d spike	W/side	7" Jack Pine	N29°E	43.91'
Set 60d spike	N/side	12" Jack Pine	S81°E	14.73'
Set 60d spike	W/side	5" White Pine	S26°W	29.50'
Set 60d spike	S/side	11" Jack Pine	S86°W	25.45'
		Metal Fence Post	North	1.5'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".