

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY MICHIGAN
RECEIVED FOR RECORD
1994 DEC 29 PM 1:55

Patricia A. Monley
REGISTER OF DEEDS

For corners in Marquette (County) **COMMISSION** Located In: Corner Code L-3

Public Land Survey	T	45N	R	25W	L-3
	T		R		
	T		R		
	T		R		
Property Controlling in Section	S		T	R	
Miscellaneous	S		T	R	
Property in Sec.	S		T	R	

RATIFIED BY PEER GROUP
P.A. 345 OF 1990
Larry J. Bassone
DATE Sept 12, 1994

LIBER **1** PAGE **216**
Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

Michael Mileski in a field survey on September 94, 19____.

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Description of original monument and accessories and/or subsequent restoration:

L-3; South One-Quarter Corner Section 1;

Originally established during U.S. Survey conducted by Martin Hall, D.S. in 1852 and monumented with a spruce pine post witnessed by a Spruce Pine 12 N61°W 75 lks. and a Spruce Pine 10 S25°E 22 lks.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3; South One-Quarter Corner Section 1;

See back of form.



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3; South One-Quarter Corner Section 1;

See back of form.

Surveyed by Michael Mileski Date 21 Nov 1994

Surveyor's Michigan License No. 39091

AP# 6476
9cc
Geo Beam

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 1" iron pipe encased in 10 inches of concrete with a plastic cap marked #27464 (Glenn Van Neste, P.S.).

Per conversation with Mr. Van Neste, this monument was found existent and of unknown origin.

Recovered monument is 0.19 feet south and 0.33 feet east of being midway and on line between controlling section corners.

State Plane Coordinates:
Grid System - NAD 83
Zone Number - 2111 Michigan North
Units - International Feet
Y = 559989.28086
X = 26151609.51299

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Let existing monumentation in place.

Set 60d spike	NW/side	11" Jack Pine	N39°E	126.70'
Set 60d spike	SW/side	5" Jack Pine	S63°E	129.36'
Set 60d spike	SE/side	6" Jack Pine	S58°W	47.14'
		Location Post		

All of the above new bearing tree marked with upper and lower face blazes and scribed "NBT".

Measurements to an existing new bearing trees as follows:

Set 60d spike	SW/side	8" Jack Pine	N46°W	13.76'
---------------	---------	--------------	-------	--------