

MAY 19 1999

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

1998 DEC 16 PM 3:21

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

MARQUETTE

(County)

Located In:

Corner Code #

Table with 3 columns: Description, Located In (Town/Range), and Corner Code #. Includes entries for Public Land Survey, Property Controlling, and Miscellaneous Property in Sec.

Patricia L. Mosley REGISTER OF DEEDS

LIBER R 2 PAGE 83

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, GERALD W. CARLSON, in a field survey on APRIL 28TH, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. Contains numerical data points for survey locations.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: L-13: Quarter Corner common to Section 36, T45N-R25W and Section 1, T44N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by: 11" Tamarack N11E, 26 L 12" Tamarack N54W, 25 L

1982: A Certificate of Survey by Gerald W. Carlson P.S. #24589 for Minatome Corporation (No Liber or page given) indicates the corner as a monumented corner. Distance S89-27'-15"W, 2638.63' to the S.W. Corner of Section 36. No accessories given.

1982: An LCRC recorded by Gerald W. Carlson P.S. #24589 in L. 5, RC Pg. 43, indicates that he found an old wood post and stump for the N.E. B.T.. He set a 5/8" X 18" Iron and Cap with a 2" X 2" X 4' stake with survey control sign. Referenced by: 15" W. Pine N48W, 15.23' 6" Tw. Cedar N02E, 12.21' 6" Cedar S74W, 14.60' 8" Cedar S29E, 8.30'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: L-13: 1998: No original corner evidence found. Found and accepted a 5/8" X 18" Iron with "MEI #24589" Cap next to a 2" X 2" wood hub in a small marshy opening along old east-west brush line. Bearings and distances to found references check very well with those recorded in L. 5, RC Pg. 43. Also found a cut-off Cedar post 1.00' South of corner. Checked Line Call (Stream 6 L, Course South, 17.00 chains [1122'] West from corner). Measured Call: West, 740', intersected +/- 5' wide N-S stream. At 1122' found no distinguishable stream. Land had water pockets all over - swampy. Distance East is 2634.88. Distance West is 2638.83.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: L-13: 1998: Replaced found 5/8" Iron and cap with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is a drivable "swamp" monument, 0.3' above ground. Measured existing references to found d.h. nails and washers: 18" W. Pine N52E, 15.25' (Carlson NBT) 7" Tw. Cedar N05E, 12.12' (Carlson NBT) 7" Cedar S75W, 14.59' (Carlson NBT) 9" Cedar S26E, 8.34' (Carlson NBT)

Set Green Steel Sign Post w/ Yellow Survey Marker Sign S80E, 2.0'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

RATIFIED BY PEER GROUP P.A. 345 OF 1990

Signature of Gary J. Pussone DATE Nov 2, 1998



Signed by Gerald W. Carlson Date 12-14-98

Surveyor's Michigan License No. 24589