

1993

COMMISSION

JOB NUMBER: 93300
SHEET NO. : 1-372
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Located In:	Corner Code #
T _{45N} R _{25W}	M-2
T _{45N} R _{24W}	A-2
T R	
T R	
S T R	
S T R	
S T R	
S T R	

RECEIVED FOR RECORD
MICHIGAN
MARQUETTE COUNTY
1993 DEC 30 PM 1:06
Office of the Registrar
of Deeds
LIBER 1 PAGE 81
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Friday, December 24, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-2: Quarter Corner common to Section 1, T45N-R25W and Section 6, T45N-R24W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:
 4" Spruce Pine N61W, 120 l
 6" Spruce Pine S70E, 26 l
 1942 - MCRC field book # 712 indicates 1" iron pipe and jack pine post set referenced by:
 10" Jack Pine N70E 50.9 ft.
 10" Jack Pine N54W 75.4 ft.
 Coordinates were also given for this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - The 1942 MCRC survey indicated that the North and South 1/2 miles in Section 1, T45N-R25W were split evenly. This is incorrect as the original notes indicate the North 1/2 mile as being 80.65 chains long. The position was calculated proportioned distance on line between the NE and SE corners of Section 1. Peer group ratification 12-20-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
 12" Jack Pine N67W 24.08 ft.
 10" Jack Pine N10W 37.09 ft.
 11" Jack Pine N24E 98.98 ft.
 9" Jack Pine N52E 51.32 ft.
 Monument is 0.40 ft. above grade.
 Bk. 4, Pg. 87



Signed by Gerald W. Carlson Date 12-29-93

Surveyor's Michigan License No. 24589