

1893

COMMISSION

JOB NUMBER: 93309
SHEET NO. : 1-377
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1993 DEC 30 PM 1:07
1 PAGE 85
Register of Deeds Stamp & File Number

Located in: Corner Code ##

1. Public Land Survey T_{45N} R_{25W} M-7
T_{45N} R_{24W} A-7
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on Monday, December 27, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M-7: Section Corner common to Sections 13 and 24, T45N-R25W 1942 - MCRC field book # 712 indicates a 1" iron pipe and and Sections 18 and 19, T45N-R24W. 1844: William A. Burt's jack pine post referenced by:
original survey notes describe the corner monument as a 5" Jack Pine N87E 16.10 ft.
wood post referenced by: 5" Jack Pine N28W 23.70 ft.
7" Spruce Pine S88W, 10 l Coordinates were also given in the field book for this
4* Spruce Pine N40E, 6 l corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1993 - Found 1" iron pipe with GcVN cap. Distance North measures 2639.7 distance South measures 2635.16. Replaced 1" iron pipe with Marquette County Survey Monument. Peer group ratification 12-13-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1993 - Replaced existing 1" iron pipe with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
7" Jack Pine N75W 8.08 ft.
10" Jack Pine N09E 18.21 ft.
6" Jack Pine N84E 31.42 ft.
9" Jack Pine S35W 35.65 ft.
Monument is 0.20 ft. above ground, and 43 ft. +/- West of the high water mark of a small lake.
Bk. 6, Pg. 16



Signed by Gerald W. Carlson Date 12-29-93

Surveyor's Michigan License No. 24589