

**SURVEY &  
REMONUMENTATION**

**FEB 21 2001**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
2000 DEC 12 PM 2:29

*Doris H. Moulton*  
REGISTER OF DEEDS

LIBER **R2** PAGE **251**  
Register of Deeds Stamp & File Number

For corners in MARQUETTE Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T 45N R 25W \_\_\_\_\_ H-7  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GERALD W. CARLSON, in a field survey on Sept. 8, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:**  
**H-7: Quarter corner to Sections 15 & 22.**  
 1852: Martin M. Hall's original subdivision survey notes describe the corner monument as a Yellow Birch post referenced by:  
 10" Spruce N54E, 7L 10" Spruce S64W, 9L
- 1942: Marquette County Road Commission Notes indicates a set 1" Iron Pipe and Tamarack Post. MCRC coordinates S. 25353.00' and W. 2986.49'.  
 Referenced by:  
 8" Jack Pine S11W, 33.1' 12" White Pine N21E, 72.7'
- 1978: Certificate of Survey recorded in L. 1 page 266 by William Donnan, RLS #17618 indicates the South quarter corner of Section 15 as a found 1" O.D. Iron Pipe. Referenced by:  
 18" White Pine N21E, 73.03' 6" Black Spruce N19W, 3.07'  
 8" Black Spruce S53W, 26.97' 10" White Pine S40E, 33.61'
- 1979: Land Corner Recordation Certificate by William R. Donnan indicates a found 1" O.D. Iron Pipe Distance West 2632.69'.  
 Referenced by:  
 18" White Pine N21E, 73.03' (1942 MCRC) 6" Black Spruce N19W, 3.07'  
 8" Black Spruce S53W, 26.97' 10" White Pine S40E, 33.61'

**RATIFIED BY PEER GROUP  
P.A. 345 OF 1990**  
*Doris H. Moulton*  
DATE 11/13/00

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
**H-7: 2000:** No original corner evidence found. Found and accepted a 1" outside diameter pipe 4' long, 1.6' above ground. Next to pipe found a 1.5' long 3" diameter post sharpened to a point 0.2' below ground.  
 Checked Line Call: East 3.13 chains (206.6'), stream 30 links, course SW. We measured 424', 12' wide, course S43W.  
 Found and measured to the above listed Donnan accessories:  
 Additional reference: 9" Dead 1/2 of tree with scribing S13W, 33.44' (believed to be 1942 MCRC NBT).

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
**H-7: 2000:** Replaced the 1" outside diameter pipe 4' long with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.15' above ground.  
 9" B. Spruce N18W, 3.06' (Donnan NBT) 9" B. Spruce S55W, 27.08' (Donnan NBT)  
 14" W. Pine S36E, 33.63' (Donnan NBT) 23" W. Pine N25E, 72.85' (MCRC NBT)  
 Green Steel Sign Post w/ Yellow Survey Marker Sign N68W, 4.00'  
 Distance East 2643.12', distance West 2633.01'.

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.  
 T45N-R25W Corner Search Sheet 2000035



Signed by Gerald W. Carlson Date 12-6-00

Surveyor's Michigan License No. 24589 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1976  
REVISED JAN., 1983  
REVISED OCT., 1996