

**SURVEY & REMONUMENTATION**

**FEB 21 2001**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

For corners in

MARQUETTE

(County)

Located In:

Corner Code #

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>45N</u> R <u>25W</u> | <u>K-6</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

2000 DEC 12 PM 2:29

*Patricia H. Monberg*  
REGISTER OF DEEDS

**LIBER R2 PAGE 255**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, GERALD W. CARLSON, in a field survey on Sept. 12, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

K-6: Quarter corner common to Sections 13 & 14.

1852: Martin M. Hall's original subdivision survey notes describe the corner monument as a Spruce Pine quarter section post referenced by:

8" Spruce Pine N70W, 19L                      5" Spruce Pine S47E, 13L

1942: Marquette County Road Commission Field Book 712 indicates a set 1" Iron Pipe and Jack Pine post with coordinates South 22773.27' and East 4969.49'. Referenced by:

6" Jack Pine N77W, 47.9'                      4" Jack Pine N65E, 24.5'

Area has since been burned over and replanted.

**RATIFIED BY PEER GROUP**  
**P.A. 345 OF 1990**

*Larry J. Busome*  
DATE 11/13/00

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

K-6: 2000: No original corner evidence found. Found and accepted a 3/4" inside diameter pipe, 1.5' above ground.

Measured Line Call: South 5.14 chains (339.2'), to bottom of basin, 50' deep. We measured 325'.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-6: 2000: Replaced the 3/4" inside diameter pipe with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.2' above ground.

Referenced by:

3" J. Pine N49E, 21.73'                      3" J. Pine S85E, 16.10'

3" J. Pine S29W, 37.09'                      3" J. Pine S71W, 25.06'

Green Steel Sign Post w/ Yellow Survey Marker Sign                      Due North, 2.73'

Distance North 2618.92', distance South 2617.60'.

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

T45N-R25W      Corner Search Sheet      2000035



Signed by Gerald W. Carlson                      Date 12-6-00

Surveyor's Michigan License No. 24589

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1976  
REVISED JAN., 1983  
REVISED OCT., 1995