

v

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 . . NR. 26 W. . .

----- Marquette ----- COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 13 and 24 -----

DESCRIPTION OF CORNER MONUMENT 1" Iron pipe with 4" Brass cap. -----

WITNESSES TO CORNER 36" W. Pine Stump - N 42 E - 89 Links -----

16" Red Pine - N 49 W - 3.49 Chains -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

In absence of definite proof, corner was established by proportionate measurement. Good section corners East and West of this corner. Two stumps, badly burned, fit this corner as probable B.T.'s.

Corner was placed and witnessed September 13, 1950.

SURVEYORS SEAL

SIGNED James C. DePater DATE 9/20/50  
REGISTERED LAND SURVEYOR