

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 N. R. 26 W


Marquette COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 29,31,30,32

CORNER MONUMENT 1" Iron Pipe driven to ground level.

DATE MONUMENT PLACED AND WITNESSED 1/11/61 with Forestry Division Survey Crew.

WITNESSES TO CORNER..... 10" Soft Maple (NBT) N 34° W 43 Links



10" Hard Maple (NBT) N 88° E 95.4 Links

22" Cedar (NBT) S 41° E 77.2 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-witnessed. Iron pipe found in south wheel track of road. Pipe was set from original B.T. according to Record, (found at Marquette County Road Commission) No original evidence present time.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler

REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 2/21/61