

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45-46 N.R. 26W


Marquette COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 5-6-31-32

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 6/21/67

WITNESSES TO CORNER..... 10" B. Oak (S62 NBT) N1°E 18.8'



13" Red Pine (S6 NBT) S63°W 65.6'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner replaced from one probable B.T.
A Y. Pine stump bearing N35°W 32 links and
remains of a down W. Pine S4°E 20 links.

No evidence of use. Position checks with good
corners 1/2 mile West and one mile North.

Corner Lies on steep hillside, facing N.W.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 10/25/67
REGISTERED LAND SURVEYOR